

Roads

Master Specification

RD-DK-S1 Supply of Pipes and Culverts

Document Information

KNet Number:	13448085
Document Version:	3
Document Date:	August 2020

DEPARTMENT FOR
INFRASTRUCTURE
AND TRANSPORT



Government of South Australia
Department for Infrastructure
and Transport

Document Amendment Record

Version	Change Description	Date
1	Initial issue (formerly R03)	28/06/19
2	Formatting for publishing	16/09/19
3	Minor edits Sections 5.1 and 6.2	August 2020

Document Management

This document is the Property of the Department for Infrastructure and Transport and contains information that is confidential to the Department. It must not be copied or reproduced in any way without the written consent of the Department. This is a controlled document and it will be updated and reissued as approved changes are made.

Contents

Contents	3
RD-DK-S1 Supply of Pipes and Culverts	4
1 General	4
2 Quality Requirements	4
3 Supply of Concrete Pipes	4
4 Supply of Small Box Culverts	5
5 Supply of Large Box Culverts	5
6 Supply of Precast Drainage Structures	6
7 Hold Points	6
8 Verification Requirements and Records	6

RD-DK-S1 Supply of Pipes and Culverts

1 General

- 1.1 This Part specifies the requirements for the supply of concrete pipes, box culverts (not exceeding 4200 mm span and 4200 mm height) and other precast drainage structures such as junction boxes, side entry pits and headwalls.
- 1.2 Documents referenced in this Part are listed below:
- a) AS 1597.1 Precast reinforced concrete box culverts - Small Culverts (not exceeding 1200 mm span and 1200 mm height).
 - b) AS 1597.2 Precast reinforced concrete box culverts - Large culverts (from 1500 mm span and up to and including 4200 mm span and 4200 mm height).
 - c) AS 1646 Rubber Joint Rings for Water Supply, Sewerage and Drainage Purposes.
 - d) AS 3610 Formwork for concrete.
 - e) AS 4058 Precast Concrete Pipes.
 - f) AS 4139 Fibre Reinforced Concrete Pipes and Fittings.
 - g) AS 9001 Quality management systems – Requirements.
- 1.3 The Contractor is responsible for ensuring that the pipes, culverts and drainage structures are designed for construction loading.

2 Quality Requirements

- 2.1 Concrete pipes, box culverts and precast drainage structures shall be manufactured in accordance with a Quality System certified to AS 9001. The Contractor shall give at least 7 days prior notice of the commencement of manufacture of the pipes.

3 Supply of Concrete Pipes

- 3.1 Unless otherwise shown on the drawings, all concrete pipes shall have Rubber Ring Joints (RRJ) with belled sockets and supplied with rubber rings complying with AS 1646. If interlocking (flush) joints are specified, the concrete pipes are to be supplied with external rubber bands for jointing (i.e. Humes "EB", Rocla "Sandband" or approved equivalent).
- 3.2 Reinforced Concrete Pipes shall comply with AS 4058. The information pursuant to Appendix B of AS 4058 is as specified on the drawings.
- 3.3 Fibre Reinforced Concrete Pipes shall comply with AS 4139. The information pursuant to Appendix A of AS 4139 is as specified on the drawings.

Damage to Reinforced Concrete Pipes

- 3.4 Any damage to reinforced concrete pipes shall be classified in accordance with AS 4058 Clause 3.4 "Workmanship and Finish" and subject to assessment in accordance with Table RD-DK-S1 3-1.

Table RD-DK-S1 3-1 Acceptability of Defects

Defect Type	Pipe Wall	Joint Surface
1	Acceptable	Not Applicable
2	Acceptable after completion of approved repair	Not Applicable
3	Reject	Not Applicable
4	Acceptable after completion of approved repair	Acceptable after completion of approved repair

Defect Type	Pipe Wall	Joint Surface
5	Acceptable after completion of approved repair	Acceptable after completion of approved repair
6	Reject	Reject
7	Reject	Reject

Damage to Fibre Reinforced Pipes

- 3.5 Fibre reinforced pipes shall be rejected if fractures and cracks wider than 0.1 mm and deeper than 0.3 mm are present.

4 Supply of Small Box Culverts

- 4.1 Small box culverts (i.e. not exceeding 1200 mm span and 1200 mm height) shall:
- comply with AS 1597.1;
 - be inverted "U" shape (crown and base type) vide AS 1597.1, Table 1.1; and
 - have plain butt joints.
- 4.2 Culverts shall be provided with a means of attaching lifting gear. The clear distance between reinforcement and the nearest surface of the culvert shall be not less than 25 mm.

5 Supply of Large Box Culverts

- 5.1 Large box culverts (i.e. from 1500 mm span and up to and including 4200 mm span and 4200 mm height) shall:
- comply with AS 1597.2;
 - Comply with ST-SD-D1;
 - be inverted "U" shape (crown and base type) vide AS 1597.2, Table 1.1; and
- 5.2 Concrete, reinforcing and formwork used for the manufacture of large box culverts shall comply with the following Parts of the Department Master Specification for Transport Infrastructure:
- ST-SC-S6 "Steel Reinforcement";
 - ST-SC-C6 "Formwork";
 - ST-SC-S7 "Supply of Concrete";
 - ST-SC-S3 "Precast Concrete Units";
 - ST-SC-S4 "Low Pressure Steam Curing of Precast Units" (where applicable); and
 - ST-SC-S5 "Heat Accelerated Curing" (where applicable).
- 5.3 The Department Master Specification is available from:
https://www.dpti.sa.gov.au/contractor_documents/specifications_-_division_CC_concrete.
- 5.4 Surface defects and deviations shall not exceed those specified in AS 3610, Table 3.4.2. Tolerances not covered by Table 3.4.2 shall comply with the following:
- the external corners of the end sections shall not depart by more than 5 mm in any direction from the corner point location defined by the drawings;
 - the tolerance on the thickness of concrete shall be + 8, - 0 mm at any section; and
 - the end faces of the units shall be square to the roof, walls and floor, when measured with a set square across the thickness of the section with a maximum deviation of 2 mm.

6 Supply of Precast Drainage Structures

General

- 6.1 If the Principal has provided drawings for drainage structures, the drawings will be based on insitu construction and the use of precast drainage structures shall be at the Contractor's risk. The Contractor is responsible for ensuring that the dimensions, design and manufacture of any precast drainage structure are suitable for use in the Works.
- 6.2 Where the design differs from that provided by the Principal, evidence shall be provided that the design satisfies the requirements of ST-SD-D1, AS5100 and/or any other relevant standard.

Steel Reinforced Drainages Structures

- 6.3 Concrete, reinforcing and formwork used for the manufacture of precast drainage structures shall comply with the following Parts of the Department Master Specification for Transport Infrastructure:
- a) ST-SC-S6 "Steel Reinforcement";
 - b) ST-SC-C6 "Formwork";
 - c) ST-SC-S7 "Supply of Concrete";
 - d) ST-SC-S3 "Precast Concrete Units";
 - e) ST-SC-S4 "Low Pressure Steam Curing of Precast Units" (where applicable); and
 - f) ST-SC-S5 "Heat Accelerated Curing" (where applicable).
- 6.4 Precast headwalls may be manufactured from geopolymer concrete complying with ST-SC-S2 "Geopolymer Concrete" in lieu of concrete complying with ST-SC-S7 "Supply of Concrete".
- 6.5 The Department Master Specification is available from:
https://www.dpti.sa.gov.au/contractor_documents/specifications_-_division_CC_concrete.

Fibre Reinforced Drainages Structures

- 6.6 Subject to obtaining prior approval, the Contractor may use fibre reinforced precast concrete drainage structures. Any such request for approval shall be accompanied by comprehensive details of:
- a) the concrete mix design;
 - b) the reinforcing fibres (including fibre material type and dosage rate);
 - c) structural calculations; and
 - d) evidence of satisfactory performance of the product, including any previous approval to use the product.
- 6.7 A proposal to use fibre reinforced precast concrete shall constitute a **Hold Point**.

7 Hold Points

- 7.1 The following is a summary of Hold Points referenced in this Part:

Table RD-DK-S1 7-1 Hold Points

Document Ref.	Hold Point	Response Time
6.7	Proposal to use fibre reinforced precast concrete	3 Working Days

8 Verification Requirements and Records

- 8.1 The Contractor shall supply written verification that the following requirements have been complied with and supply the verification with the lot package.

Table RD-DK-S1 8-1 Verification Requirements

Document Ref.	Subject	Property	Test Procedure	Test Frequency	Acceptance Limits
3	Reinforced Concrete Pipes: Manufacturing Requirements	As specified in AS 4058, Table 4.2	Appendices to AS 4058	As specified in AS 4058, Section 5	As specified in AS 4058, Section 4
3	Fibre Reinforced Pipes: Manufacturing Requirements	Product certification by a JAS-ANZ accredited certification body that the requirements of AS 4139 Appendix N are complied with.			
4	Small Box Culvert Manufacturing Requirements	Ultimate Load	AS 1597.1, Section 3	Required in the first instance for each size of box culvert or in the first instance any design change	As specified in AS 1597, Part 1, Section 3
		Water Absorption Test	-	Not required (vide AS 1597.1, Clause 1.4)	-
5	Large Box Culverts Manufacturing Requirements	Concrete Requirements, vide all ST-SC-S and C Parts (excl. St-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)
6	Precast Drainage Structures: Manufacturing Requirements	Concrete Requirements, vide all ST-SC-S & C Parts (excl. ST-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)	As specified in all ST-SC-S & C Parts (excl. ST-SC-C4)